

ADDENDUM NO. 2

Renovations (Old Derrick's Hardware Building)
NORTH COMMUNITY CHALLENGE CENTER
4583 Savannah Highway
North, SC 29112

August 24, 2015

1. **FLOORING – NEW CONCRETE SLAB POURED ON TOP OF EXISTING SLAB:**

Refer to Floor Plan, New Concrete Slab Poured on Top of Existing Slab. Contractors shall figure in their Bid the following Procedure for New Concrete Floor Slab:

Clean Existing Floor of All Debris and Foreign Matter and Apply a Bonding Agent as recommended by the Concrete Manufacturer.

Pour a 6" Slab at the Front of the Building and Taper Down to 2" at the Rear of the Building. The Ramp at Door No. 1 will have to be Adjusted and the 4'-0" high Wall will have to be moved to accommodate the new floor. Door No. 1 will remain as shown.

Door No. 21 shall be Replaced along with the Door Frame and Framing System. New Frame will be Metal – as specified. New Door will be 3'-0" x 6'-8" Metal and have a Lite with Safety Glass, as shown on Sheet 2. Door and Frame shall be Painted, as specified.

Concrete is to be Reinforced with Fibers-Poured-In System.